

Exhibit “2”

11-006

**Contract No. 11 – Roamingwood Sewer and Water Association
Agent of South Wayne County Water and Sewer Authority
Salem and Lake Townships, Wayne County, Pa**

**TO: LaBella Associates
1000 Dunham Drive
Dunmore, PA 18512**

DATE: May 18, 2017

ATTN: David Osborne, P.E.

PRIME CONTRACTOR'S NAME

James T. O'Hara, Inc.
205 Old School House Road
Covington Township, PA 18444
PHONE: (570) 842-2140
FAX: (570) 842-8205
E-MAIL: jtobids@gmail.com

CONTRACTOR'S STAMP

Approved by:
Robert O'Hara
James T. O'Hara, Inc.

PRODUCT SPECIFICATION: 02559 Low Pressure Sewers and Appurtenances

NAME & NO: Para 2.9 Curb Stop and Check Valve

DRAWING NO: 207

SUBCONTRACTOR: N/A

**SUPPLIER: Central Clay
101 Scott Street
Wilkes Barre PA 18702**

MANUFACTURER: The Lateral Connection Corp.

NO. OF COPIES: 1

(A/E USE ONLY)

☐ REVIEWED ☐ REVISE AND RESUBMIT
☐ REJECTED ☒ FURNISH AS NOTED

Corrections or comments made on the shop drawings during this review do not relieve the contractor from compliance with requirements of the drawings and specifications. This check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents. The contractor is responsible for confirming and correlating all quantities and dimensions; selecting fabrication processes and techniques of construction; coordinating his work with that of all other trades; and performing his work in a safe and satisfactory manner

LaBella Associates, D.P.C.

By:

David Osborne

Date: 5/31/2017

E/A STAMP

PROVIDE GR-4150 MODEL

ROAMINGWOOD-000009




TLC

THE LATERAL CONNECTION CORP.

**Performance™ Series
Compression Fittings,
Valves and
Saddles**

CEPEX®

www.lateralconnection.com



PP Ball Valves & Curb Stops/Checks

Performance™ Series

Description

- Polypropylene Ball Valves, Curb Stops & Curb/Check Assemblies for PE pressure piping applications.

Tube

- IPS(OD) • For use on HDPE Pipe SDR 7.3 thru SDR 17.
(Ball Valve Sizes 3/4" - 2", Curb Stop & Curb/Check Assembly Sizes 1-1/4" - 2")
- For use on Sch 40/80 PVC Pipe with SS Gripper Ring.
(Ball Valve Sizes 3/4" - 2", Curb Stop & Curb/Check Assembly Sizes 1-1/4"-2")
- CTS(OD) • For use on Certified PE Pipe SDR 9 & SDR 11.
(Ball Valve Sizes 3/4" - 2", Curb Stop & Curb/Check Assembly Sizes 1-1/4"-2")
- For use on Cross Linked Pipe PE SDR 9 for Cold Water Only.
(Ball Valve Sizes 3/4" - 2", Curb Stop & Curb/Check Assembly Sizes 1-1/4" - 2")
- For use on Copper Pipe with CTS SS Gripper Ring (Ball Valve Sizes 3/4" - 1")

Working pressure


- At 73° F (23° C) 1/2" - 2" rated to 200 PSI

Features

- Compression (IPS & CTS) & Threaded (FIPT) end connectors available.
- Curb Stop handle has built in torque overload protection (ratcheting handle).
- Fully serviceable.
- EPDM O-Rings.
- Color Coded.
- Extremely smooth handle operation.
- UV stabilized.
- Extensively used worldwide.
- ISO 9001 certified.

Applications


- Water Distribution
- Low Pressure Sewer
- Reclaim Water
- Industrial
- Leachate Collection
- Irrigation
- Many other uses



1-1/4" - 2" Curb/Check Assemblies



1-1/4" - 2" Curb Stops



3/4" - 2" Ball Valves

PP Compression Fittings

Performance™ Series

Description

- Polypropylene (PP) Compression Fittings for PE pressure piping applications.

Tube

- IPS(OD) • For use on HDPE Pipe SDR 7.3 thru SDR 17. (Sizes 1/2" - 4")
 - For use on Sch 40/80 PVC Pipe with SS Gripper Ring. (Sizes 1/2" - 2")
- CTS(OD) • For use on Certified PE Pipe SDR 9 & SDR 11. (Sizes 3/4" - 2")
 - For use on Cross Linked Pipe PE SDR 9 for Cold Water Only. (Sizes 3/4" - 2")
 - For use on Copper Pipe with CTS SS Gripper Ring. (Sizes 3/4" - 1")

Working pressure

- At 73° F (23° C) 1/2" - 2" rated to 200 PSI
- 3" - 4" rated to 150 PSI

Features

- Ease of installation.
- One source for all your IPS & CTS needs.
- Color coded.
- UV stabilized.
- Extensively used worldwide.
- ISO 9001 certified.

Applications

- Water distribution
- Low Pressure Sewer
- Industrial Leachate
- Collection Irrigation
- Many other uses

Specifications

- IPS(OD) • ASTM-F714 / ASTM-D3035 / ASTM-D-1599-99 / NSF 61
- CTS(OD) • ASTM-D2737 / ASTM-D1248 / ASTM-D-1599-99 / NSF 61 / CSA B137.1



Comp x Comp

Coupling & Adapter	90° Tee	90° Elbow	End Cap & SS Gripper Ring
IPS 1/2" - 4" CTS 3/4" - 2"	IPS 3/4" - 4" CTS 3/4" - 2"	IPS 1/2" - 4" CTS 3/4" - 2"	IPS 1/2" - 2"
Comp x Female Thread	IPS 1/2" - 3" CTS 3/4" - 2"	IPS 1/2" - 3" CTS 3/4" - 2"	IPS 1/2" - 2" CTS 3/4" - 1"
Comp x Comp Reducing	IPS 3/4" - 2" CTS 1" - 2"	IPS 3/4" - 3" CTS 1" - 2"	
Comp x Male Thread	IPS 1/2" - 4" CTS 3/4" - 2"		




FIG.	Parts	Material
1	Split Ring	POM
2	Nut	PP
3	Insert	PP
4	O-ring	NBR 70 (POTABLE WATER)
5	Body	PP